

SL. No.	ITEM AND SPECIFICATION	QUANTITY
1	<p>Tile Flexure Strength Testing Machine Capacity 200 KG. (Hand Operated)</p> <p>For clay roofing tiles (Mangalore Pattern) & Cement concrete flooring tiles. Double lever (Leverage 1:12) loading machine Load applied by flow of lead shots to automatically stopped when the sample brakes. The loading rate of 45 to 55 kg/min with accuracy of load indications is + 3%. The sample should be monitored between rollers of 40 mm. dia.</p>	One

Ansu V

Lab in Charge of Material testing lab and
 Assistant Professor in Civil Engineering.

13-10-2017



Daya
 30/10/17
 Jwr HoD-CE